

*Tempo Musical Productions presents:*

## **“The Sound of Music”**

*January 1997  
at the Church Hill Theatre*

### ***Set Painting/Construction Requirements***

#### ***Set Painting***

##### **I, 3**

- Door flat (face): wooden panelling.
- Door (for above): both sides wooden.
- Masking flat behind door flat: wooden panelling merging into blackness.
- Truck for desk: plain black.

##### **I, 5**

- 6' x 12' (2 of), 4' x 12', 1' x 12' flats: Peach walls with decorations (dedo line, etc.) darker. Panelling at bottoms.
- Rostrum and treads: to match panelling above.

##### **I, 7**

- 5' x 12' window flat: plain black.

##### **I, 9**

- Rostrum, treads plinths and urns: to match stone of balustrade (from Lyceum).
- Italian Cyprus trees: dark green.

##### **II, 7**

- 4' x 12' (3 of - one is door flat), 2' x 12' (window) flats: dark stone. Suggestion of arch/moulding around door/window.
- 4' x 18' (2 of), 8' x 8' flats: dark stone wall to match above.
- Statue surround/base: dark stone to match above.
- Profiled 'Mountain' front-piece: naturalistic mountain grass, etc.

## *Set Construction*

### **I, 3**

- Bookcase flat checked for points to attach braces either side on reverse.
- Truck to be mounted on castors (if not already).
- Door to be mounted in door flat (hinged on left-side looking at front of flat).
- Masking flat to be hinged onto door flat (left-side looking at front of flats).

### **I, 5**

- 6' x 12' (2 of), 1' x 12' flats to be checked for brace points, cleats and lines (1' flat goes to SL of two 6' flats).
- 4' x 12' flat to be checked for brace points.
- Balustrade has to be able to stand freely, or with stage weights.

### **I, 6**

- Trellising to be checked that it is okay to be mounted onto truck.

### **I, 7**

- 5' x 12' window flat to have 1' high fill-in piece attached at back to give impression of window stopping 1' from floor. Curtains (with pelmet) to be attached.

### **I, 9**

- Cyprus trees to be made (existing french braces used for support).

### **II, 6**

- Releases for Nazi banner to be constructed.
- Golden eagle/Release mechanism to be constructed.

### **II, 7**

- 2' x 12' window flat to be constructed.
- Profile flat for front of 'Mountain' to be constructed.
- Return on door and window to be deepened to give impression of 'thick' walls.